PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT

REVISED LAYOUT PLAN FOR SUPER MEGA MIXED USE INTEGRATED INDUSTRIAL PARK PROJECT OF JANTA LAND PROMOTERS PVT. LTD AT SECTOR 66A, 82 & 83 SAS NAGAR

PROMOTERS:-
JANTA LAND PROMOTERS PVT. LTD.
CORPORATE OFFICE : SCO 39 -42 ,SECTOR -82 ,
SAS NAGAR(MOHALI)

TOTAL CLU AREA:- ——— 1

AREA UNDER C.L.U I ---------- = 215.28 ACRES
AREA UNDER C.L.U II ---------- = 9.43 (5.85 + 0.74 + 0.54 + 2.30) ACRES ——— 2
AREA UNDER C.L.U III ---------- = 0.82 ACRES ---------- 3
AREA UNDER C.L.U IV ---------- = 1.65 ACRES ---------- 4
AREA UNDER C.L.U V ---------- = 0.69 ACRES ---------- 5
AREA UNDER C.L.U VI ---------- = 3.485 ACRES ---------- 6
AREA UNDER C.L.U VII ---------- = 0.8565 ACRES ---------- 7 (new area)
AREA UNDER C.L.U VIII ---------- = 18.21 ACRES ---------- 8
AREA UNDER ACQUISITION ---------- = 273.31 ACRES ---------- 9
SCHEME AREA ---------- = 286.34 ACRES ---------- 11
AREA FOR WHICH AGREEMENT CANCELED ---------- 6.25 ACRES ---------- 12
AREA EARMARKED FOR R. RASTA AND DELETED FROM PROJECT ——— = 1.92 ACRES ——— 13
NEW SCHEME AREA AFTER DELETION OF AREAS ——— = 278.171 ACRES ——— 14
AREA EXCLUDED FROM SUPER MEGA & INCLUDED
IN THE PREVIOUS APPROVED MEGA PROJECT ---------- = 2.75 + 0.51 = 3.26 ACRES ---------- 15

AREA INCLUDED TWO TIMES IN THE C.L.U ---------- = 0.64 ACRES ——— 16
BALANCE AREA FOR PLANNING ---------- = 14-15-16= 274.271 ACRES ——— 17
RESERVED AREA = 1.96 ACRES ---------- 18
PLANNED AREA = 17-18 ---------- 19
NET PLANNED AREA EXCLUDING GOVT. ACQUISITION = 272.31-36.80 = 235.51 ACRES ——— X

GROSS F.A.R. ALLOWED = 2.00
PERMITTED F.A.R. (2.00) ——— = 39.77,601.12 SQ.FTS.
A) COMMERCIAL COMPONENT ALLOWED (15%) = 35.326 ACRES

COMMERCIAL PROVIDED

- COMMERCIAL POCKET I = 1.21 acres = F.A.R provided 106000 sq.fts.
- COMMERCIAL POCKET II = 3.02 Acres = F.A.R provided 395000 sq.fts.
- COMMERCIAL POCKET III = 0.71 Acres = F.A.R provided 88442 sq.fts.
- COMMERCIAL POCKET III A = 1.21 Acres = F.A.R provided 158400 sq.fts.
- COMMERCIAL POCKET IV = 0.66 Acres = F.A.R provided 86400 sq.fts.
- COMMERCIAL AREA UNDER RESIDENTIAL POCKET 1 FALCON VIEW = 0.18 Acres = F.A.R provided 7600 sq.fts.
- COMMERCIAL AREA UNDER RESIDENTIAL POCKET 2C2 SKY GARDEN = 0.85 Acres = F.A.R provided 2300 sq.fts.
- COMMERCIAL AREA UNDER RESIDENTIAL POCKET 2A GALAXY HEIGHT = 0.013 Acres= F.A.R provided 550 sq.fts.

TOTAL COMMERCIAL PROVIDED = 8.44 Acres = 8.44/602 sq.fts. say 8.44 lacs sq. fts

CORRESPONDING LAND UTILIZED = 7.053 ACRES
BALANCED AREA = 35.326 - 7.053 ACRES = 28.273 ACRES
BALANCE FAR = 22,32,909.12 SQ.FTS.

B) INDUSTRIAL AREA ALLOWED (MIN. 55%)
INDUSTRIAL AREA TAKEN = 60% = 141.306 ACRES

(30% of the industrial area)

C) ADDITIONAL ACTIVITIES ALLOWED AS PER SUPER MEGA POLICY = 42.39 acres

POCKET I (HOTEL SITE I)	= 9.08 ACRES
HOTEL 1	= 44536.96 sq. yds (8.92 ACRES)
HOTEL 2	= 40837.92 sq. yds (8.83 ACRES)
HOTEL A	= 40000.00 sq. yds (8.82 ACRES)
= 14.57 ACRES	= 70911.69 sq. yds (1.47 ACRES)
INSTITUTIONAL AREA	= 0.52 ACRES
RELIGIOUS BUILDING	= 0.56 ACRES
PLOT NO 5004	= 1612.16 sq.yds (0.26 ACRES in supermega and rest 0.07 acres in mega project)
PLOT NO. 1599	= 1000 sq. yds (0.21 ACRES)
SR. SEC. SCHOOL	= 11394.75 sq. yds (2.35 ACRES)
NURSERY SCHOOL 1	= 0.75 ACRES
COMMUNITY CENTRE	= 2.76 ACRES
GRID STATION	= 0.93 ACRES
NR. CUM PRIMARY SCHOOL II	= 0.75 ACRES
DISPENSARY	= 0.50 ACRES
NR. CUM PRIMARY SCHOOL III	= 0.82 ACRES
TOTAL AREA PROVIDED UNDER INSTITUTIONAL	= 23.53 ACRES

D)BALANCED INDUSTRIAL PLOTS = TOTAL INDUSTRIAL AREA TAKEN - AREA UNDER INSTITUTIONAL USE

E) PERMISSIBLE SALEABLE AREA UNDER INDUSTRIAL PLOTS 65% = 76.55 ACRES
F) INDUSTRIAL PLOT PROVIDED AS PER DETAIL = 48.52ACRES (34.18%) (LIST ATTACHED ALONGSIDE)

G) RESIDENTIAL COMPONENT ALLOWED (BALANCE AREA) = 87.151 ACRES

DETAILS OF RESIDENTIAL COMPONENT

F.A.R. ALLOWED AT 87.188 ACRES = 75,92,595.12 SQ.FTS

- POCKET I = 34.02 acres F.A.R = 42.10 lac sq.fts.
- POCKET 2A = 4.22 acres F.A.R = 4.59 lac sq. fts
- POCKET 2B = 3.59 acres F.A.R = 3.50 lac sq. fts
- POCKET 2C2 = 6.21 acres F.A.R = 6.76 lac sq. fts

- RESIDENTIAL POCKET III = 1.45 acres F.A.R = 1.26 lac sq.fts.
- RESIDENTIAL POCKET VI = 2.00 acres F.A.R = 1.04 lac sq.fts. (exclusively reserved for E.W.S)
- RESIDENTIAL POCKET VII = 2.16 acres FAR = 1.12 lac sq.fts. (exclusively reserved for E.W.S)
- RESIDENTIAL POCKET IV = 3.33 acres FAR = 2.50 lac sq.fts.

(NOT TO BE SOLD TILL PROPER APPROACH IS ACQUIRED)
TOTAL = 56.98 acres = FAR provided 62.87 lac sq.fts.

2. PERMISSIBLE DWELLING UNITS =235.551X 175/5=8244.285 = 8245 UNITS
DWELLING UNITS TO BE TAKEN FOR CONSTRUCTION AS PER APPROVED BUILDING PLANS (TILL DATE & PROPOSED FOR SITE NO. III & IV = 3216
3. AREA REQUIRED FOR E.W.S = 10 % OF THE UNITS = TAKEN FOR CONSTRUCTION = 321.60 = 322 UNITS
AREA REQUIRED FOR 322 UNITS @ 80 UNITS PER ACRES = 4.025 ACRES
AREA ALREADY TRANSFERRED TO GMADA = 4.16 ACRES

OPEN SPACE REQUIRED 6% = 14.12 ACRES = 5.05%

AREA UNDER PARKS			
S. NO	PARK DETAILS	NO.	AREA IN SQ. YDS
1	PARK 1	1	2339.26
2	PARK 2	1	3451.97
3	PARK 3	1	3420.85
4	PARK 4	1	980.55
5	PARK 5	1	772.51
6	PARK 6	1	1383.87
7	PARK 7	1	321.46
8	PARK 8	1	380.06
9	PARK 9	1	2859.13
10	PARK 10	1	14987.6
11	PARK 11	1	790.51
12	PARK 12	1	3334.05
13	PARK 13	1	2858.63
14	PARK 14	1	3673.71
15	PARK 15	1	2214.87
16	PARK 16	1	260 49
17	PARK 17	1	20561 76
18	PARK 18	1	1394.24
19	PARK 19	1	1055.55
20	PARK 20	1	1944.44
	TOTAL	20	68985.51
	IN ACRES		14.25

LIST OF RESERVED AREAS

S.NO.	RESERVED AREA	NO.	AREA IN SQ. YDS
1	R.A.1	1	471.15
2	R.A.2	1	435.48
3	R.A.3	1	2217.20
4	R.A.4	1	1437.79
5	R.A.5	1	626.04
6	R.A.6	1	184.05
7	R.A.7	1	2975.23
8	R.A.8	1	237.28
9	R.A.9	1	914.43
	TOTAL	9	9498.65
	IN ACRES		1.96

I) AREA PROVIDED UNDER 2 S.T.P= 1277.01 + 1802.74 sq. yds
WATER WORKS = 546.40 sq. yds
E.G.S = 0.93 acres
TOTAL AREA = 1.68 acres

POPULATION CALCULATION			
		UNITS	POPULATION @ 5 PERSONS PER UNIT
1	TOTAL NO. OF UNITS TAKEN FOR CONSTRUCTION =	3216	16080
2	E.W.S UNITS @ 80 UNITS PER ACRE FOR 4.16 ACRES =	333	1665
3	COMMERCIAL POPULATION @ 100 PERSONS PER ACRES	7.053 ACRES	705.3
4	INSTITUTIONAL POPULATION @ 100 PERSONS PER ACRES	21.99 ACRES	2199
	TOTAL POPULATION		20649.3

UTILITIES REQD FOR THIS POPULATION			
		NO. OF UNITS REQD	PROVIDED
1	HIGH SCHOOL	1	1
2	NURSERY CUM PRIMARY SCHOOL	4	4
3	RELIGIOUS BUILDING	1	1
4	DISPENSARY	1	1
5	COMMUNITY CENTRE	1	1

NOTE:-

1.PLOTS WHICH PARTIALLY FALLS IN INDUSTRIAL MEGA PROJECT AND PARTIALLY IN INDUSTRIAL SUPER MEGA PROJECT SHALL BE ALLOWED FINANCIAL OR PHYSICAL PARAMETERS I.KE COVERAGE ,F.A.R. ETC CONCESSIONS AS PER INDUSTRIAL MEGA PROJECT POLICY ONLY.
2. ALL PUBLIC BUILDINGS REQUIRED FOR RESIDENTIAL POPULATION SHALL BE PROVIDED WITH IN RESIDENTIAL POCKET OUT OF AREA EARMARKED FOR INSTITUTIONAL AREA.
3. PLOTS/AREAS SHOWN UNDER GOVT. ACQUISITION SHALL NOT BE DEVELOPED AND SOLD UNTIL OWNERSHIP IS TRANSFERRED IN THE NAME OF THE FIRM.
4. F.A.R CALCULATION FOR AREA UNDER ACQUISITION SHALL FINALLY BE DETERMINED AND ALLOWED AT THE TIME OF DETAILED APPROVAL FOR RESIDENTIAL POCKETS I TO VII , COMMERCIAL POCKETS I TO IV, INSTITUTIONAL I TO IV AND INDUSTRIAL (I.T. TOWER) AND OTHER SUCH AREAS ETC.
4. SITES THROUGH WHICH SEWER DRAIN IS PASSING SHALL BE DEVELOPED ONLY AFTER CONSULTING ENGINEER WING GMADA W.R.T THIS DRAIN
5. THE SEWERAGE NETWORK OF SUPERMEGA PROJECT HAS ALREADY BEEN CONNECTED WITH GMADA S.T.P LOCATED AT SECTOR- 83 VIDE LETTER NO. GMADA / DIV ENGINEER (PH-112014/1110 DATED 21.3.2014 AND HENCE HAS BEEN REMOVED FROM THE SUPERMEGA PROJECT.

TITLE:- REVISED LAYOUT PLAN

ARCHITECT:-

OWNER:-

ORIENTATION N E W S

DATE:- 21.12.2016
DRAWING NO :-DC/TP/JLPL/LP/08
DEALT BY:- KANWAL
CHKD. BY:-

SCALE:- 1"- 220'-0"

DHAM CONSULTANTS
ARCHITECT & PLANNERS,
S.C.O -358-359, SECTOR 34 -A,
CHANDIGARH
PHONE NO. 5009617

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT

LEGEND :-

- RESIDENTIAL AREA
- PUBLIC BUILDING
- RESERVED AREA
- ACQUISITION AREA
- PARKS
- NEW BOUNDARY LINE (super mega project)
- RAILWAY TRACK
- REVENUE RASTA
- COMMERCIAL AREA
- INDUSTRIAL PLOTS (not to be sold till the time land/approach available)
- INDUSTRIAL PLOTS
- OPEN AREA
- BOUNDARY LINE (mega project)
- RESERVED GREEN
- AREA INCLUDED IN MEGA PROJECT AND EXCLUDED FROM SUPER MEGA PROJECT
- NOT TO BE SOLD INDUSTRIAL PLOTS (RESERVED INDUSTRIAL PLOTS)
- NEW PLOTS DEVELOPED IN ALREADY APPROVED AREA
- AREA DELETED FROM THE OVERALL PROJECT SITE = 6.25 + 1.92 ACRES
- NEW C.L.U 18.21 ACRES